



भा. कृ. अनु. प. –केन्द्रीय शुष्क क्षेत्र अनुसंधान संस्थान
ICAR - Central Arid Zone Research Institute
जोधपुर (राजस्थान) 342 003 / Jodhpur (Rajasthan) 342 003
Website: www.cazri.res.in, Email: director.cazri@icar.gov.in
Phone No. 0291 – 2786584(Dir.)/2786485(CAO)/2785981(AO) FAX: 0291 – 2788706(Dir.)/2786498(PME)

REGISTERED POST



F.No. 17(5) P&F of Iron Ladder/AINP on VPM/18-19/Adm.V

Dated: 01.12.2018

To,

M/S.....

.....

.....

JODHPUR.

Sub: Quotation for providing and fixing of Iron Ladder at Rodent Building, ICAR- CAZRI, Jodhpur.

Dear Sir(s),

You are requested to kindly quote your lowest rates keeping in view the following conditions in respect of the articles indicated overleaf/as per statement enclosed (Schedule to tender).

1. No advance payment will be made. However, the payment is normally made within 30 days from the date of receipt of Bill for execution the work **in good condition as per order**.
2. The quantity proposed in the quotation may be increased or decreased at the discretion of the authority while placing the order.
3. Quotation not found according to specification will be rejected/not considered.
4. The firm should also supply a copy of the authorized dealership certificate of the item, if applicable
5. Quotation should remain valid for 3 months from the date of quotation.
6. No. Form 'C' & 'D' for sales tax will be issued. Payment will be made at full rate, if applicable. However, the firm is required to produce the valid sales tax Registration No. The firm should also indicate PAN/TIN as per Income Tax Rules.
7. The Rates **should be clearly indicated in figure as well as in words**. While quoting the rates, it may be clearly indicated whether the items are inclusive or exclusive of ST, CST etc. in terms of percentage or in absolute term.
8. Works will have to be completed normally within 30 days from the date of issue of work order or as mentioned in the supply order unless such extension is allowed by the Institute **failing which suitable penalty as indicated in the work order will be imposed**.
9. Director, CAZRI, Jodhpur reserves the right to accept or reject any or all the quotation without assigning any reason.
10. All bids must be accompanied by a bid security / **EMD of Rs. nil/-** of the estimated value of the cost, in the form of a Demand Draft of a scheduled commercial bank in India, in favour of **ICAR Unit-CAZRI, Jodhpur**. Without EMD quotation will not be considered.
11. The firm awarded the contract may/will have to furnish a performance security in the form of Bank Guarantee as per the proforma to be supplied along with work order or FDR pledged to "**ICAR Unit - CAZRI, Jodhpur**" from a scheduled Commercial Banks for an amount which may vary from 5% to 10% of the value of the contract at the discretion of Director, which should remain valid for six months.
12. The quotation may be sent to the office by courier/Registered Post/Speed Post in sealed cover super scribed with providing and fixing of Iron Ladder at Rodent Building, ICAR- CAZRI, Jodhpur.
13. The quotation must be reached to this Office on or before **15.12.2018 at 3.00 PM** which it will not be considered. The quotation should be dropped in the Tender Box placed in the Adm.V.

Yours faithfully,

ASSISTANT ADMINISTRATIVE OFFICER (V)



भा. कृ. अनु. प. —केन्द्रीय शुष्क क्षेत्र अनुसंधान संस्थान
ICAR - Central Arid Zone Research Institute
जोधपुर (राजस्थान) 342 003 / Jodhpur (Rajasthan) 342 003
Website: www.cazri.res.in, Email: director.cazri@icar.gov.in
Phone No. 0291 – 2786584(Dir.)/2786485(CAO)/2785981(AO) FAX: 0291 – 2788706(Dir.)/2786498(PME)



F.No. 17(5) P&F of Iron Ladder/AINP on VPM/18-19/Adm.V

Dated: 01.12.2018

निविदा प्रपत्र

(इस फार्म को निविदा प्रपत्र के साथ जमा कराना आवश्यक है)

निदेशक, केन्द्रीय शुष्क क्षेत्र अनुसंधान संस्थान, जोधपुर निम्नलिखित कार्य के लिए सीमित मोहरबन्द निविदाये आमंत्रित करते हैं।

- कार्य का नाम : **Providing and fixing of Iron Ladder at Rodent Building, ICAR-CAZRI, Jodhpur.**
- निविदादाता फर्म का नाम/पूर्ण पता :
- टेलीफोन/मोबाईल नम्बर :
- निविदादाता फर्म का : PAN No.
:GST/TIN No.
- बैंक का विवरण : बैंक का नाम.....
: पता
- बैंक का IFS Code :
- बैंक का खाता नम्बर :
- निविदा प्रपत्र की कीमत : रू. शून्य
- धरोहर (बयाना) राशि : रू. nil
- कार्य पूर्ण करने की अवधि : एक माह
- निविदा जमा कराने की अंतिम तिथि : 15/12/2018 at 3.00 PM
- निविदा कार्य की विस्तृत सूचना काजरी की वेबसाईट <http://www.cazri.res.in> पर देखी जा सकती है।
- निविदा प्रपत्र काजरी, जोधपुर की वेबसाईट से भी डाउनलोड किये जा सकते हैं।

निविदादाता के मोहर सहित हस्ताक्षर

Name of work:- Providing & Fixing Iron Ladder at Rodent building ICAR-CAZRI, Jodhpur

Sl. No.	Code No	Description	Qty	Unit	Rate	Amount
1		EARTH WORK				
	2.8	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.				
	2.8.1	All kinds of soil.	0.5	cum	@.....	
2		CONCRETE WORK				
	4	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets etc. up to floor five level, excluding the cost of centering, shuttering and finishing :				
	4.1.3	1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	1	cum	@.....	
3	10	STEEL WORK				
	10.25	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.				
	10.25.1	In stringers, treads, landings etc. of stair cases including use of chequered plate wherever required, all complete.	475	Kg.	@.....	
	10.26	Providing and fixing hand rail of approved size by welding etc. to steel ladder railing, balcony railing and staircase railing including applying a priming coat of approved steel primer.				
	10.26.1	M.S. tube.	75	Kg.	@.....	
4	11	FLOORING				
	11.3	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete.				
	11.3.1	40mm thick with 20mm nominal size stone aggregate.	4.5	sqm	@.....	
5	13	FINISHING				
	13.61	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :				
	13.61.1	Two or more coats on new work	35	sqm	@.....	
6	15	DISMANTLING & DEMOLISHING				
	15.9	Demolishing stone rubble masonry manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge:				
	15.9.2	In cement mortar	0.3	cum	@.....	
Total						

(Rupees only)

Signature with seal of tenderer